



Basic 2.0		
Length	196 ft 10 in	(15x [13 ft 1 in] = 196 ft 10 in)
Width	105 ft	(4x [26 ft 3 in] = 105 ft)
Area	20,667 sq ft	0.5 Acre
Height	13 ft 1 in	
Snow load ¹	7.31 psf	
Crop load	3.13 psf	
Installation loads	1.46 psf	
Windspeed ²	105 mph	
¹ In heavy snow areas a snow melt heating to be applied		
² Reduction factors apply		
Service Building Basic 2.0		
Length	105 ft	(8x [13 ft 1 in] = 105 ft)
Width	39 ft 4 in	(1x [39 ft 4 in] = 39 ft 4 in)
Area	4,133 sq ft	
Height	13 ft 1 in	
Energy and Irrigation room included with separation walls		
Packing handling and office space by local contractor inside this prefab building		