



Expert 1.0		
Length	144 ft 4 in	(11x [13 ft 1 in] = 144 ft 4 in)
Width	157 ft 6 in	(6x [26 ft 3 in] = 157 ft 6 in)
Area	22,733 sq ft	0.5 Acre
Height	15 ft 9 in	
Snow load ¹	7.31 psf	
Crop load	3.13 psf	
Installation loads	1.46 psf	
Windspeed ²	105 mph	
¹ In heavy snow areas a snow melt heating to be applied		
² Reduction factors apply		
Service Building Expert 1.0		
Length	91 ft 10 in	(7x [13 ft 1 in] = 91 ft 10 in)
Width	39 ft 4 in	(1x [39 ft 4 in] = 39 ft 4 in)
Area	3,617 sq ft	
Height	15 ft 9 in	
Energy and Irrigation room included with separation walls		
Packing handling and office space by local contractor inside this prefab building		