



Basic 1.0		
Length	105 ft	(8x [13 ft 1 in] = 105 ft)
Width	105 ft	(4x [26 ft 3 in] = 105 ft)
Area	11,022 sq ft	0.25 Acre
Height	13 ft 1 in	
Snow load <sup>1</sup>	7.31 psf	
Crop load	3.13 psf	
Installation loads	1.46 psf	
Windspeed <sup>2</sup>	105 mph	
<sup>1</sup> In heavy snow areas a snow melt heating to be applied		
<sup>2</sup> Reduction factors apply		
Service Building Basic 1.0		
Length	78 ft 9 in	(6x [13 ft 1 in] = 78 ft 9 in)
Width	26 ft 3 in	(1x [26 ft 3 in] = 26 ft 3 in)
Area	2,067 sq ft	
Height	13 ft 1 in	
Energy and Irrigation room included with separation walls		
Packing handling and office space by local contractor inside this prefab building		